## PENETRATIONS

1. SUBCONTRACTOR IS RESPONSIBLE FOR ALL CUTTING, PATCHING, AND REPAIR TO PENETRATIONS ASSOCIATED WITH THIS SCOPE OF WORK. THIS INCLUDES ALL PENETRATIONS THROUGH FIRE RATED WALLS. STELLAR'S APPROVAL IS REQUIRED BEFORE PENETRATIONS ARE MADE. IF SUBCONTRACTOR DOES NOT HAVE STELLAR'S APPROVAL PRIOR TO MAKING PENETRATION, IT SHALL BE RESPONSIBILITY OF SUBCONTRACTOR TO REPAIR PENETRATIONS THAT ARE IN THE WRONG LOCATION, INCLUDING ENTIRE WALL PANELS OR BLOCKS.
2. THE SUBCONTRACTOR SHALL HIRE THE ROOFING COMPANY, TO CUT THE MEMBRANE AND INSULATION, FLASH AND SEAL ROOF PENETRATIONS AS TO MAINTAIN WARRANTY OF THE ROOFING MEMBRANE. SUBCONTRACTOR IS RESPONSIBLE FOR PROPER LOCATION AND CUTTING THE ROOF DECK WITH ROOFING COMPANY REPRESENTATIVE ON SITE.
3. PENETRATIONS SHALL BE INSTALLED PER DETAILS FOR APPROPRIATE WALL TYPE AND ENVIRONMENTAL CONDITIONS.
4. CONDUIT & PIPE SHALL PASS THROUGH WALLS ONLY AT 90 DEGREES AND TO BE RUN PARALLEL OR PERPENDICULAR TO BUILDING COLUMN LINES.

## SEALANTS AND GASKETS

1. CAULK, SEALANTS OR OTHER CHEMICAL MATERIALS REQUIRED SHALL BE FDA APPROVED AND WILL NOT "YELLOW", MILDEW, OR PROMOTE THE GROWTH OF BACTERIA. MATERIALS SHALL PURCHASED PER EQUIPMENT MANUFACTURES RECOMMENDATION, UNLESS PROJECT SPECIFIC BRAND IS SPECIFIED. SELECTED CHEMICAL MUST BE APPROVED BY THE OWNER.
2. CAULK SEALANTS OR OTHER CHEMICAL MATERIALS SHALL BE APPLIED IN A GOOD WORKMAN LIKE MANNER. MINIMIZE EXCESS APPLICATION AND WIPE CLEAN ANY EXCESS THAT OCCURS. CHEMICAL MATERIALS SHALL NOT ENTER THE PRODUCT STREAM. ANY CHEMICAL MATERIALS FOUND IN THE PRODUCT STREAM SHALL BE MITIGATED TO OWNER APPROVAL AT THE COST OF THE INSTALLATION SUBCONTRACTOR.
3. ALL ELASTOMERS SUCH AS BUT NOT LIMITED TO SEALS, GASKETS, HOSES, AND O-RINGS SHALL BE MADE OF FDA APPROVED MATERIALS AND SHALL BE APPROVED BY OWNER.

## THREADED CONNECTIONS

1. BOLTED CONNECTIONS SHALL BE DOUBLE NUTTED UNLESS OTHERWISE SPECIFIED.
2. IN PROCESS WASHDOWN AREAS, HANGER RODS SHALL BE STAINLESS STEEL ROD WITH THREADED ENDS. FULLY THREADED RODS WILL NOT BE PERMITTED IN SUCH AREAS. FULLY THREADED RODS ARE ACCEPTABLE IN NON-WASHDOWN AREAS.
3. IN NON-WASHDOWN AREAS, NO MORE THAN 3-5 TURNS OF EXPOSED THREADS IS ALLOWED.
4. IN WASHDOWN AREAS, ACORN NUTS SHALL BE PLACED ON EXPOSED THREADS. THE ACORN NUT CAN BE USED AS THE JAM NUT WHEN DOUBLE NUTTING BOLTED CONNECTIONS.
5. THREADED RODS SUPPORTING PIPE & CONDUIT HANGERS IN INTERSTITIAL SPACE SHALL HAVE AN ACORN NUT AT THE BOTTOM TO COVER SHARP ENDS.

## TELECOMMUNICATIONS

1. COORDINATE FINAL LOCATIONS OF ALL EQUIPMENT WITH THE APPROPRIATE TRADE.
2. CONDUIT SHALL PASS THROUGH WALLS ONLY AT 90 DEGREES AND SHALL BE RUN PARALLEL OR PERPENDICULAR TO WALLS.
3. ALL UNDERGROUND CONDUIT RUNS ENTERING THE BUILDING SHALL BE SEALED TO PREVENT THE ENTRANCE OF MOISTURE AND GASES.
4. CONDUIT SHALL BE AS DESCRIBED IN THE SPECIFICATIONS AND THESE GENERAL NOTES.
5. ALL WORK SHALL BE PER NEC 2020 AND ALL OTHER LOCAL, STATE AND NATIONALLY ENFORCED CODES.
6. SEAL ALL PENETRATIONS THROUGH FIRE WALLS TO MAINTAIN THE RATING OF WALL/FLOOR.
7. THESE DOCUMENTS PERTAIN TO TELECOM ONLY. THIS DESIGN SHALL NOT BE USED TO QUALIFY OTHER DISCIPLINES NOR SHALL IT BE RESPONSIBLE FOR OTHER DISCIPLINE REQUIREMENTS OR PROPERTY ASSETS NOT A PART OF THE TELECOM CONTRACT.
8. REFER TO THE VITAL FARMS CABLE STANDARD DOCUMENTS FOR ADDITIONAL INSTALLATION REQUIREMENTS.
9. DEVICES MOUNTED TO CMU WALLS SHALL BE INSTALLED FLUSH WITH WALL IN THE WELFARE SPACES. SURFACE MOUNTING IS ACCEPTABLE IN NON-WELFARE SPACES.
10. FAILURE TO FOLLOW THESE REQUIREMENTS WILL BE CONSIDERED INADEQUATE WORK. ALL DISCREPANCIES SHALL BE CORRECTED WITH NO EXPENSE TO STELLAR OR FACILITY OWNER.
11. LL CONDUIT PENETRATIONS GOING THROUGH AREAS WITH A DIFFERENCE IN TEMPERATURE OF 15 DEGREES OR MORE SHALL BE SEALED PER DETAIL DT5001-A1.
12. CONDUIT INDOORS SHALL BE EMT 20'-0" ABOVE FINISHED FLOOR IN DRY AREAS WHERE NOT SUBJECT TO DAMAGE. COMPRESSION TYPE FITTINGS SHALL BE USED FOR 1-1/2" AND SMALLER SET SCREW MAY BE USED FOR SIZES LARGER THAN 1-1/2". CONDUIT BELOW 20'-0" SHALL BE AL IN DRY AREAS. EMT CONDUIT MAY BE USED IN OFFICE SPACES. CONDUIT OUTDOORS ABOVE GRADE SHALL BE IMC. CONDUIT OUTDOORS BELOW GRADE SHALL BE SCH 40 PVC. CONDUIT IN PROCESS AREAS SHALL BE ALUMINUM.
13. ALL WALL MOUNTED EQUIPMENT AND CONDUIT IN PROCESS AREAS SHALL HAVE A 1" STANDOFF. ALL ATTACHMENTS TO IMP WALLS SHALL USE "FAB LOCK" SCREWS. VERTICAL CONDUIT DROPS MAY BE GANGED TOGETHER USING STAINLESS FLATBAR SPACED 1" FROM WALL AND 1" FROM ADJACENT CONDUIT. REFER TO DRAWINGS DT5000 & DT5002 FOR CONDUIT SUPPORT & ELECTRICAL EQUIPMENT MOUNTING DETAILS.
14. NO UNISTRUT OR ALLTHREAD IS ALLOWED IN PROCESS/WASHDOWN SPACES. REFER TO DRAWING DT5000 FOR CONDUIT SUPPORT DETAILS.
15. MINIMIZE HORIZONTAL RUNS OF CONDUIT IN PROCESS/WASHDOWN SPACES. UTILIZE WALK-ON CEILING SPACE FOR HORIZONTAL TRANSITIONS. ORIENT DEVICES SO THAT STANDING WATER DOES NOT ACCUMULATE ON DEVICES.
16. TELEPHONE/DATA/WIRELESS ACCESS POINTS - THE BUILDING ELECTRICAL CONTRACTOR WILL PROVIDE A SYSTEM OF CONDUIT, FITTINGS, AND BOXES IN THE OFFICES AND OTHER FINISHED SPACES, FROM DEVICE LOCATION TO THE ABOVE CEILING SPACE OR ABOVE JOISTS ONLY IF NO CEILING. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL DIRECTION AND SCOPE. PARTICULARILY DRAWING EE1101 FOR THE ELECTRICAL ENVIRONMENTAL ZONE PLAN. COORDINATE WITH ELECTRICAL CONTRACTOR.
17. SECURITY SYSTEM - THE ELECTRICAL CONTRACTOR WILL PROVIDE A SYSTEM OF CONDUIT, FITTINGS, AND BOXES IN ALL AREAS, FROM DEVICE LOCATION TO THE ABOVE CEILING SPACE OR ABOVE JOISTS ONLY IF NO CEILING. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL DIRECTION AND SCOPE. PARTICULARILY DRAWING EE1101 FOR THE ELECTRICAL ENVIRONMENTAL ZONE PLAN. COORDINATE WITH ELECTRICAL CONTRACTOR.
18. ALL DEVICES, JACKS, AND CABLES SHALL BE LABELED PER THE VITAL FARMS CABLE STANDARD.

## PROCESS TELECOMMUNICATIONS SHEET LIST

| SHEET NO. | SHEET NAME |
|---|---|
| DT0001 | PROCESS TELECOMMUNICATION GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS |
| DT1011 | PROCESS TELECOM OVERALL SITE CAMERA LOCATIONS |
| DT1101 | PROCESS TELECOM OVERALL 1ST FLOOR PLAN |
| DT1110 | PROCESS TELECOM OVERALL FIRST FLOOR MDF/IDF FUNCTIONAL AREA PLAN |
| DT1111 | PROCESS TELECOM OVERALL 1ST FLOOR CAMERA LOCATIONS |
| DT1112 | PROCESS TELECOM OVERALL 1ST FLOOR WAP LOCATIONS |
| DT1113 | PROCESS TELECOM OVERALL 1ST FLOOR ACCESS CONTROL LOCATIONS |
| DT1201 | PROCESS TELECOM OVERALL 2ND FLOOR PLAN |
| DT1211 | PROCESS TELECOM OVERALL 2ND FLOOR CAMERA LOCATIONS |
| DT1212 | PROCESS TELECOM OVERALL 2ND FLOOR WAP LOCATIONS |
| DT1213 | PROCESS TELECOM OVERALL 2ND FLOOR ACCESS CONTROL LOCATIONS |
| DT1401 | PROCESS TELECOM OVERALL ROOF PLAN |
| DT4111 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 1 SECTOR 1 |
| DT4112 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 1 SECTOR 2 |
| DT4121 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 1 |
| DT4122 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 2 |
| DT4123 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 3 |
| DT4124 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 4 |
| DT4125 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 5 |
| DT4126 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 6 |
| DT4131 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 3 SECTOR 1 |
| DT4132 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 3 SECTOR 2 |
| DT4134 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 3 SECTOR 4 |
| DT4141 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 4 SECTOR 1 |
| DT4142 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 4 SECTOR 2 |
| DT4143 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 4 SECTOR 3 |
| DT4151 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 1 |
| DT4152 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 2 |
| DT4153 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 3 |
| DT4154 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 4 |
| DT4155 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 5 |
| DT4161 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 6 SECTOR 1 |
| DT4162 | PROCESS TELECOM 1ST FLOOR PLAN, AREA 6 SECTOR 2 |
| DT4212 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 1 SECTOR 2 |
| DT4221 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 2 SECTOR 1 |
| DT4222 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 2 SECTOR 2 |
| DT4224 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 2 SECTOR 4 |
| DT4242 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 4 SECTOR 2 |
| DT4243 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 4 SECTOR 3 |
| DT4252 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 5 SECTOR 2 |
| DT4253 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 5 SECTOR 3 |
| DT4254 | PROCESS TELECOM 2ND FLOOR PLAN, AREA 5 SECTOR 4 |
| DT4421 | PROCESS TELECOM ROOF PLAN, AREA 2 SECTOR 1 |
| DT4434 | PROCESS TELECOM ROOF PLAN, AREA 3 SECTOR 4 |
| DT4452 | PROCESS TELECOM ROOF PLAN, AREA 5 SECTOR 2 |
| DT5000 | CONDUIT SUPPORTS |
| DT5001 | CONDUIT PENETRATIONS |
| DT5002 | STANDARD ELECTRICAL POWER DETAILS |
| DT5003 | ACCESS CONTROL DETAILS SHEET 1 |
| DT6001 | PROCESS TELECOM CIRCUIT SCHEDULE - IT |
| DT6002 | PROCESS TELECOM CIRCUIT SCHEDULE - OT |
| DT6011 | MDF 2M11 LAYOUT & DETAIL |
| DT6021 | MDF 2M21 LAYOUT & DETAIL |
| DT6031 | IDF 201 LAYOUT & DETAIL |
| DT6032 | IDF 202 LAYOUT & DETAIL |
| DT6033 | IDF 203 LAYOUT & DETAIL |
| DT6034 | IDF 204 LAYOUT & DETAIL |
| DT6035 | IDF 205 LAYOUT & DETAIL |
| DT6036 | IDF 206 LAYOUT & DETAIL |
| DT6101 | MDF FIBER SCHEDULES |
| DT6102 | MDF 2M11 SWITCH SCHEDULES |
| DT6103 | MDF 2M21 SWITCH SCHEDULES |
| DT6104 | IDF 201 SWITCH SCHEDULES |
| DT6105 | IDF 202 SWITCH SCHEDULES |
| DT6106 | IDF 203 SWITCH SCHEDULES |
| DT6107 | IDF 204 SWITCH SCHEDULES |
| DT6108 | IDF 205 SWITCH SCHEDULES |
| DT6109 | IDF 206 SWITCH SCHEDULES |
| Grand total: 68 | |

## ANNOTATION SYMBOLS LEGEND

### CONSTRUCTION NOTE TAG

5 — NOTE #

NOTE: THE CONSTRUCTION NOTE IDENTIFIES APPLICABLE CONSTRUCTION NOTES IN DRAWING VIEWS. NOTE # REFERS TO CONSTRUCTION NOTE LEGEND ON EACH SHEET.

### PROCESS EQUIPMENT NUMBERING & TAGGING

EQUIPMENT NUMBERING — TAGS DEPICTED AS

AAAbbBBB
- EQUIPMENT IDENTIFIER
- PROCESS FUNCTIONAL AREA NUMBER
- SEQUENTIAL NUMBER
- LINE NUMBER (OPTIONAL)

SHORT DESC. (TWO LINES) — AAAbbBBB

NOTE: REFER TO DRAWING DG0100 FOR EQUIPMENT NUMBER ("EQUIPMENT ID") ASSIGNMENTS

### BUILDING EQUIPMENT NUMBERING & TAGGING

EQUIPMENT NUMBERING — TAGS DEPICTED AS

AAA-b
- EQUIPMENT IDENTIFIER
- SQUENTIAL NUMBER

SHORT DESC. (TWO LINES) — AAA-b

## DATA DEVICE LEGEND

- IT
- OT
- ACCESS CONTROL
- CAMERA
- WIRELESS ACCESS POINT

## ACCESS CONTROL

- DEVICE TYPE
- DOOR FUNCTION
- DOOR NUMBER

AA-bb-BBBBB

## DEVICE TYPE / FUNCTION

| | |
|---|---|
| CR | CARD READER |
| AC | ACCESS CONTROL |
| BO | EMPLOYEE BADGE OUT |

## DEVICE AND JACK IDENTIFIER

- DEVICE TYPE
- PROCESS FUNCTIONAL AREA NUMBER
- 2-DIGIT SEQUENTIAL DEVICE NUMBER

AAA-bbBB

## DEVICE TYPES

| | |
|---|---|
| CAM | SECURITY CAMERA |
| CPU | COMPUTER |
| DT | PROCESS GENERAL DATA DROP |
| TV | TV / DISPLAY |
| WAP | WIRELESS ACCESS POINT |

## LEGEND

| | |
|---|---|
| | POWER POLE BY OTHERS |
| S | SINGLE POLE SINGLE THROW SWITCH (SPST) |
| | VOICE/DATA OUTLET, BACK BOX AND CONDUIT STUBBED |
| | DATA OUTLET, PROVIDE (1) CABLE UNLESS NOTED OTHERWISE. # NEXT TO DEVICE INDICATES JACK IDENTIFICATION. |
| FP | WALL MOUNTED FURNITURE FEED, BACK BOX AND CONDUIT STUBBED ABOVE CEILING OR TO BAR JOISTS BY ELECTRICAL CONTRACTOR. PROVIDE CAT 6A CABLES AS NOTED. # NEXT TO DEVICE INDICATES JACK IDENTIFICATION. |
| | FLOOR OUTLET, FLOOR BOX AND CONDUIT STUBBED ABOVE CEILING OR TO BAR JOISTS BY ELECTRICAL CONTRACTOR. PROVIDE CAT 6A CABLES AS NOTED. # NEXT TO DEVICE INDICATES JACK IDENTIFICATION. |
| CR | ELECTRONIC CARD READER |
| DC | DOOR CONTACT |
| DDC | DOUBLE DOOR CONTACT |
| EL | ELECTRIC DOOR LOCK (PROVIDED BY DOOR SUPPLIER) |
| OH | OVERHEAD DOOR CONTACT |
| IC | INTERCOM AND CAMERA STATION |
| EM | REMOTE DOOR RELEASE |
| PTH | POWER TRANSFER HINGE (PROVIDE BY DOOR SUPPLIER) |
| C | CAMERA |
| J | JUNCTION BOX (SIZE PER N.E.C.) |

## ABBREVIATIONS

| | |
|---|---|
| AC | ABOVE COUNTER TOP, SEE ARCH ELEVATIONS |
| AFF | ABOVE FINISHED FLOOR |
| AFG | ABOVE FINISHED GRADE |
| AL | ALUMINUM |
| ATS | AUTOMATIC TRANSFER SWITH |
| BATT | BATTERY |
| BC | BELOW COUNTER |
| BFF | BELOW FINISHED FLOOR |
| BFG | BELOW FINISHED GRADE |
| BOCT | BOTTOM OF CABLE TRAY, MEASUERD FROM FIRST FLOOR SLAB |
| CMU | CONCRETE MASONRY UNIT |
| CONC | CONCRETE |
| CONTR | CONTRACTOR |
| CPT | CONTROL POWER TRANSFORMER |
| CT | CURRENT TRANSFORMER |
| CU | COPPER |
| DISC | DISCONNECT |
| DN | DOWN |
| EF | EXHAUST FAN |
| EL | ELEVATION |
| EWC | ELECTRIC WATER COOLER |
| FVNR | FULL VOLTAGE NON-REVERSING |
| GFCI | GROUND FAULT CIRCUIT INTERRUPTER |
| HOA | HAND-OFF-AUTO |
| IMP | INSULATED METAL PANEL |
| INST | INSTANTANEOUS |
| LNS | LINE NETWORK SWITCH |
| MCC | MOTOR CONTROL CENTER |
| MDP | MAIN DISTRIBUTION PANEL |
| MSB | MAIN SWITCHBOARD |
| NC | NORMALLY CLOSED |
| NO | NORMALLY OPEN |
| PNL | PANEL |
| RCP | REFRIGERATION CONTROL PANEL |
| RTD | RESISTANCE TEMPERATURE DETECTOR |
| T/CONC | TOP OF CONCRETE |
| T/GRATING | TOP OF GRATING |
| T/M | THERMAL MAGNETIC |
| TOH | TOP OF HANGER |
| TYP | TYPICAL |
| UON | UNLESS NOTED OTHERWISE |
| V-PH-HZ | VOLTS-PHASE-HERTZ |
| WP | WEATHERPROOF |
| XFMR | TRANSFORMER |

## PROCESS SHEET IDENTIFIER

- LEVEL 1 DISCIPLINE DESIGNATOR
- LEVEL 2 DISCIPLINE DESIGNATOR
- SHEET TYPE DESIGNATOR
- SHEET SUB-TYPE DESIGNATOR
- 2-DIGIT SEQUENCE DESIGNATOR
- 2-DIGIT SEQUENCE DESIGNATOR

DX####-##

- *SUB-SECTOR DESIGNATOR
- *SECTOR DESIGNATOR
- *AREA DESIGNATOR

*APPLICABLE TO PLANS ONLY

## DISCIPLINE DESIGNATOR

| | | | |
|---|---|---|---|
| DC | PROCESS CONTROLS | DQ | PROCESS EQUIPMENT |
| DE | PROCESS ELECTRICAL | DT | PROCESS TELECOMMUNICATION |
| DG | PROCESS GENERAL/OVERALL | DU | PROCESS UTILITIES |
| DP | PROCESS PIPING | SK | PROCESS SKETCHES |

## SHEET TYPE DESIGNATOR

0 GENERAL - SYMBOLS, LEGENDS, NOTES, ETC.
1 PLANS
2 ELEVATIONS AND PROFILES
3 SECTIONS
4 LARGE SCALE VIEWS
5 DETAILS
6 SCHEDULES AND DIAGRAMS
7 USER DEFINED
8 USER DEFINED
9 3D REPRESENTATIONS

## SHEET SUB-TYPE DESIGNATOR

0 FOUNDATIONS
1 FIRST FLOOR / SLAB
2 ELEVATED FLOOR STRUCTURES AND FRAMING, MEZZANINE
3 INTERSTITIAL SPACE
4 ROOF STRUCTURE / FRAMING
5 ROOF RAISED PLATFORM
6 FIRST FLOOR REFLECTED CEILING
7 ELEVATED FLOOR STRUCTURE AND FRAMING, MEZZANINE REFLECTED CEILING
8 INTERSTITIAL SPACE REFLECTED CEILING (OPTIONAL)

## DEMOLITION DRAWINGS

DDX####-##

INDICATES DEMOLITION DRAWING

OWNER

PROJECT INFORMATION

VITAL FARMS
EGG CENTRAL 2
SEYMOUR,IN


stellar
TAKING SOLUTIONS FURTHER

OPERATING AS:
THE STELLAR GROUP
2900 HARTLEY ROAD, JACKSONVILLE, FL 32257 (904) 260-2900
WWW.STELLAR.NET


SEAL

Professional certification. I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed professional architect/engineer under the laws of the state of IN.

CONSULTANT


The Stellar Group, Inc.
All rights reserved. No part of this work may be used, reproduced, distributed, displayed, or otherwise communicated in any form or by any means without the prior written consent of The Stellar Group, Inc.


REVISIONS

| NO. | DESCRIPTION | DATE |
|---|---|---|
| A | DESIGN DEVELOPMENT 2 | 12/12/2025 |
| B | ISSUED FOR BID | 01/16/2026 |
| C | REVISED FOR BID | 02/06/2026 |
| D | GMP ISSUE | 04/02/2026 |

| | |
|---|---|
| DATE ISSUED: | 12/12/2025 |
| DESIGNED BY: | KDK |
| REVIEWED BY: | MAM |
| AIEOR: | |
| PROJECT NUMBER: | 07645 |

SHEET TITLE

PROCESS TELECOMMUNICATION GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS

SHEET ID

DT0001


4/3/2026 1:22:00 AM Autodesk Docs://07645_Vital Farms Egg Central Station 2/07645_VF EGG STA 2_D_R23.rvt