PENETRATIONS

1. SUBCONTRACTOR IS RESPONSIBLE FOR ALL CUTTING, PATCHING, AND REPAIR TO PENETRATIONS ASSOCIATED WITH THIS SCOPE OF WORK. THIS INCLUDES ALL PENETRATIONS THROUGH FIRE RATED WALLS. STELLAR'S APPROVAL IS REQUIRED BEFORE PENETRATIONS ARE MADE. IF SUBCONTRACTOR DOES NOT HAVE STELLAR'S APPROVAL PRIOR TO MAKING PENETRATION, IT SHALL BE RESPONSIBILITY OF SUBCONTRACTOR TO REPAIR PENETRATIONS THAT ARE IN THE WRONG LOCATION, INCLUDING ENTIRE WALL PANELS OR BLOCKS.
2. THE SUBCONTRACTOR SHALL HIRE THE ROOFING COMPANY, TO CUT THE MEMBRANE AND INSULATION, FLASH AND SEAL ROOF PENETRATIONS AS TO MAINTAIN WARRANTY OF THE ROOFING MEMBRANE. SUBCONTRACTOR IS RESPONSIBLE FOR PROPER LOCATION AND CUTTING THE ROOF DECK WITH ROOFING COMPANY REPRESENTATIVE ON SITE.
3. PENETRATIONS SHALL BE INSTALLED PER DETAILS FOR APPROPRIATE WALL TYPE AND ENVIRONMENTAL CONDITIONS.
4. CONDUIT & PIPE SHALL PASS THROUGH WALLS ONLY AT 90 DEGREES AND TO BE RUN PARALLEL OR PERPENDICULAR TO BUILDING COLUMN LINES.

SEALANTS AND GASKETS

1. CAULK, SEALANTS OR OTHER CHEMICAL MATERIALS REQUIRED SHALL BE FDA APPROVED AND WILL NOT "YELLOW", MILDEW, OR PROMOTE THE GROWTH OF BACTERIA. MATERIALS SHALL PURCHASED PER EQUIPMENT MANUFACTURES RECOMMENDATION, UNLESS PROJECT SPECIFIC BRAND IS SPECIFIED. SELECTED CHEMICAL MUST BE APPROVED BY THE OWNER.
2. CAULK SEALANTS OR OTHER CHEMICAL MATERIALS SHALL BE APPLIED IN A GOOD WORKMAN LIKE MANNER, MINIMIZE EXCESS APPLICATION AND WIPE CLEAN ANY EXCESS THAT OCCURS. CHEMICAL MATERIALS SHALL NOT ENTER THE PRODUCT STREAM. ANY CHEMICAL MATERIALS FOUND IN THE PRODUCT STREAM SHALL BE MITIGATED TO OWNER APPROVAL AT THE COST OF THE INSTALLATION SUBCONTRACTOR.
3. ALL ELASTOMERS SUCH AS BUT NOT LIMITED TO SEALS, GASKETS, HOSES, AND O-RINGS SHALL BE MADE OF FDA APPROVED MATERIALS AND SHALL BE APPROVED BY OWNER.

THREADED CONNECTIONS

1. BOLTED CONNECTIONS SHALL BE DOUBLE NUTTED UNLESS OTHERWISE SPECIFIED.
2. IN PROCESS WASHDOWN AREAS, HANGER RODS SHALL BE STAINLESS STEEL ROD WITH THREADED ENDS. FULLY THREADED RODS WILL NOT BE PERMITTED IN SUCH AREAS. FULLY THREADED RODS ARE ACCEPTABLE IN NON-WASHDOWN AREAS.
3. IN NON-WASHDOWN AREAS, NO MORE THAN 3-5 TURNS OF EXPOSED THREADS IS ALLOWED.
4. IN WASHDOWN AREAS, ACORN NUTS SHALL BE PLACED ON EXPOSED THREADS. THE ACORN NUT CAN BE USED AS THE JAM NUT WHEN DOUBLE NUTTING BOLTED CONNECTIONS.
5. THREADED RODS SUPPORTING PIPE & CONDUIT HANGERS IN INTERSTITIAL SPACE SHALL HAVE AN ACORN NUT AT THE BOTTOM TO COVER SHARP ENDS.

TELECOMMUNICATIONS

1. COORDINATE FINAL LOCATIONS OF ALL EQUIPMENT WITH THE APPROPRIATE TRADE.
2. CONDUIT SHALL PASS THROUGH WALLS ONLY AT 90 DEGREES AND SHALL BE RUN PARALLEL OR PERPENDICULAR TO WALLS.
3. ALL UNDERGROUND CONDUIT RUNS ENTERING THE BUILDING SHALL BE SEALED TO PREVENT THE ENTRANCE OF MOISTURE AND GASES.
4. CONDUIT SHALL BE AS DESCRIBED IN THE SPECIFICATIONS AND THESE GENERAL NOTES.
5. ALL WORK SHALL BE PER NEC 2020 AND ALL OTHER LOCAL, STATE AND NATIONALLY ENFORCED CODES.
6. SEAL ALL PENETRATIONS THROUGH FIRE WALLS TO MAINTAIN THE RATING OF WALL/FLOOR.
7. THESE DOCUMENTS PERTAIN TO TELECOM ONLY. THIS DESIGN SHALL NOT BE USED TO QUALIFY OTHER DISCIPLINES NOR SHALL IT BE RESPONSIBLE FOR OTHER DISCIPLINE REQUIREMENTS OR PROPERTY ASSETS NOT A PART OF THE TELECOM CONTRACT.
8. REFER TO THE VITAL FARMS CABLE STANDARD DOCUMENTS FOR ADDITIONAL INSTALLATION REQUIREMENTS.
9. DEVICES MOUNTED TO CMU WALLS SHALL BE INSTALLED FLUSH WITH WALL IN THE WELFARE SPACES. SURFACE MOUNTING IS ACCEPTABLE IN NON-WELFARE SPACES.
10. FAILURE TO FOLLOW THESE REQUIREMENTS WILL BE CONSIDERED INADEQUATE WORK. ALL DISCREPANCIES SHALL BE CORRECTED WITH NO EXPENSE TO STELLAR OR FACILITY OWNER.
11. LL CONDUIT PENETRATIONS GOING THROUGH AREAS WITH A DIFFERENCE IN TEMPERATURE OF 15 DEGREES OR MORE SHALL BE SEALED PER DETAIL DT5001-A1.
12. CONDUIT INDOORS SHALL BE EMT 20'-0" ABOVE FINISHED FLOOR IN DRY AREAS WHERE NOT SUBJECT TO DAMAGE. COMPRESSION TYPE FITTINGS SHALL BE USED FOR 1-1/2" AND SMALLER SET SCREW MAY BE USED FOR SIZES LARGER THAN 1-1/2". CONDUIT BELOW 20'-0" SHALL BE AL IN DRY AREAS. EMT CONDUIT MAY BE USED IN OFFICE SPACES. CONDUIT OUTDOORS ABOVE GRADE SHALL BE IMC. CONDUIT OUTDOORS BELOW GRADE SHALL BE SCH 40 PVC. CONDUIT IN PROCESS AREAS SHALL BE ALUMINUM.
13. ALL WALL MOUNTED EQUIPMENT AND CONDUIT IN PROCESS AREAS SHALL HAVE A 1" STANDOFF. ALL ATTACHMENTS TO IMP WALLS SHALL USE "FAB LOCK" SCREWS. VERTICAL CONDUIT DROPS MAY BE GANGED TOGETHER USING STAINLESS FLATBAR SPACED 1" FROM WALL AND 1" FROM ADJACENT CONDUIT. REFER TO DRAWINGS DT5000 & DT5002 FOR CONDUIT SUPPORT & ELECTRICAL EQUIPMENT MOUNTING DETAILS.
14. NO UNISTRUT OR ALLTHREAD IS ALLOWED IN PROCESS/WASHDOWN SPACES. REFER TO DRAWING DT5000 FOR CONDUIT SUPPORT DETAILS.
15. MINIMIZE HORIZONTAL RUNS OF CONDUIT IN PROCESS/WASHDOWN SPACES. UTILIZE WALK-ON CEILING SPACE FOR HORIZONTAL TRANSITIONS. ORIENT DEVICES SO THAT STANDING WATER DOES NOT ACCUMULATE ON DEVICES.
16. TELEPHONE/DATA/WIRELESS ACCESS POINTS - THE BUILDING ELECTRICAL CONTRACTOR WILL PROVIDE A SYSTEM OF CONDUIT, FITTINGS, AND BOXES IN THE OFFICES AND OTHER FINISHED SPACES, FROM DEVICE LOCATION TO THE ABOVE CEILING SPACE OR ABOVE JOISTS ONLY IF NO CEILING. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL DIRECTION AND SCOPE. PARTICULARILY DRAWING EE1101 FOR THE ELECTRICAL ENVIRONMENTAL ZONE PLAN. COORDINATE WITH ELECTRICAL CONTRACTOR.
17. SECURITY SYSTEM - THE ELECTRICAL CONTRACTOR WILL PROVIDE A SYSTEM OF CONDUIT, FITTINGS, AND BOXES IN ALL AREAS, FROM DEVICE LOCATION TO THE ABOVE CEILING SPACE OR ABOVE JOISTS ONLY IF NO CEILING. SEE ELECTRICAL DRAWINGS FOR ADDITIONAL DIRECTION AND SCOPE. PARTICULARILY DRAWING EE1101 FOR THE ELECTRICAL ENVIRONMENTAL ZONE PLAN. COORDINATE WITH ELECTRICAL CONTRACTOR.
18. ALL DEVICES, JACKS, AND CABLES SHALL BE LABELED PER THE VITAL FARMS CABLE STANDARD.

PROCESS TELECOMMUNICATIONS SHEET LIST

SHEET NO.	SHEET NAME
DT0001	PROCESS TELECOMMUNICATION GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS
DT1011	PROCESS TELECOM OVERALL SITE CAMERA LOCATIONS
DT1101	PROCESS TELECOM OVERALL 1ST FLOOR PLAN
DT1110	PROCESS TELECOM OVERALL FIRST FLOOR MDF/IDF FUNCTIONAL AREA PLAN
DT1111	PROCESS TELECOM OVERALL 1ST FLOOR CAMERA LOCATIONS
DT1112	PROCESS TELECOM OVERALL 1ST FLOOR WAP LOCATIONS
DT1113	PROCESS TELECOM OVERALL 1ST FLOOR ACCESS CONTROL LOCATIONS
DT1201	PROCESS TELECOM OVERALL 2ND FLOOR PLAN
DT1211	PROCESS TELECOM OVERALL 2ND FLOOR CAMERA LOCATIONS
DT1212	PROCESS TELECOM OVERALL 2ND FLOOR WAP LOCATIONS
DT1213	PROCESS TELECOM OVERALL 2ND FLOOR ACCESS CONTROL LOCATIONS
DT1401	PROCESS TELECOM OVERALL ROOF PLAN
DT4111	PROCESS TELECOM 1ST FLOOR PLAN, AREA 1 SECTOR 1
DT4112	PROCESS TELECOM 1ST FLOOR PLAN, AREA 1 SECTOR 2
DT4121	PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 1
DT4122	PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 2
DT4123	PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 3
DT4124	PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 4
DT4125	PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 5
DT4126	PROCESS TELECOM 1ST FLOOR PLAN, AREA 2 SECTOR 6
DT4131	PROCESS TELECOM 1ST FLOOR PLAN, AREA 3 SECTOR 1
DT4132	PROCESS TELECOM 1ST FLOOR PLAN, AREA 3 SECTOR 2
DT4134	PROCESS TELECOM 1ST FLOOR PLAN, AREA 3 SECTOR 4
DT4141	PROCESS TELECOM 1ST FLOOR PLAN, AREA 4 SECTOR 1
DT4142	PROCESS TELECOM 1ST FLOOR PLAN, AREA 4 SECTOR 2
DT4143	PROCESS TELECOM 1ST FLOOR PLAN, AREA 4 SECTOR 3
DT4151	PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 1
DT4152	PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 2
DT4153	PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 3
DT4154	PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 4
DT4155	PROCESS TELECOM 1ST FLOOR PLAN, AREA 5 SECTOR 5
DT4161	PROCESS TELECOM 1ST FLOOR PLAN, AREA 6 SECTOR 1
DT4162	PROCESS TELECOM 1ST FLOOR PLAN, AREA 6 SECTOR 2
DT4212	PROCESS TELECOM 2ND FLOOR PLAN, AREA 1 SECTOR 2
DT4221	PROCESS TELECOM 2ND FLOOR PLAN, AREA 2 SECTOR 1
DT4222	PROCESS TELECOM 2ND FLOOR PLAN, AREA 2 SECTOR 2
DT4242	PROCESS TELECOM 2ND FLOOR PLAN, AREA 4 SECTOR 2
DT4253	PROCESS TELECOM 2ND FLOOR PLAN, AREA 5 SECTOR 3
DT4254	PROCESS TELECOM 2ND FLOOR PLAN, AREA 5 SECTOR 4
DT4421	PROCESS TELECOM ROOF PLAN, AREA 2 SECTOR 1
DT4434	PROCESS TELECOM ROOF PLAN, AREA 3 SECTOR 4
DT4452	PROCESS TELECOM ROOF PLAN, AREA 5 SECTOR 2
DT5000	CONDUIT SUPPORTS
DT5001	CONDUIT PENETRATIONS
DT5002	STANDARD ELECTRICAL POWER DETAILS
DT6001	PROCESS TELECOM CIRCUIT SCHEDULE - IT
DT6002	PROCESS TELECOM CIRCUIT SCHEDULE - OT
DT6011	MDF 2M11 LAYOUT & DETAIL
DT6021	MDF 2M21 LAYOUT & DETAIL
DT6031	IDF 201 LAYOUT & DETAIL
DT6032	IDF 202 LAYOUT & DETAIL
DT6033	IDF 203 LAYOUT & DETAIL
DT6034	IDF 204 LAYOUT & DETAIL
DT6035	IDF 205 LAYOUT & DETAIL
DT6036	IDF 206 LAYOUT & DETAIL
DT6101	MDF FIBER SCHEDULES
DT6102	MDF 2M11 SWITCH SCHEDULES
DT6103	MDF 2M21 SWITCH SCHEDULES
DT6104	IDF 201 SWITCH SCHEDULES
DT6105	IDF 202 SWITCH SCHEDULES
DT6106	IDF 203 SWITCH SCHEDULES
DT6107	IDF 204 SWITCH SCHEDULES
DT6108	IDF 205 SWITCH SCHEDULES
DT6109	IDF 206 SWITCH SCHEDULES
Grand total: 64	

ANNOTATION SYMBOLS LEGEND

CONSTRUCTION NOTE TAG

5 — NOTE #

NOTE: THE CONSTRUCTION NOTE IDENTIFIES APPLICABLE CONSTRUCTION NOTES IN DRAWING VIEWS. NOTE # REFERS TO CONSTRUCTION NOTE LEGEND ON EACH SHEET.

PROCESS EQUIPMENT NUMBERING & TAGGING

EQUIPMENT NUMBERING | TAGS DEPICTED AS

AAAbbBBB
- EQUIPMENT IDENTIFIER
- PROCESS FUNCTIONAL AREA NUMBER
- SEQUENTIAL NUMBER
- LINE NUMBER (OPTIONAL)

SHORT DESC.
(TWO LINES)
AAAbbBBB

NOTE: REFER TO DRAWING DG0100 FOR EQUIPMENT NUMBER ("EQUIPMENT ID") ASSIGNMENTS

BUILDING EQUIPMENT NUMBERING & TAGGING

EQUIPMENT NUMBERING | TAGS DEPICTED AS

AAA-b
- EQUIPMENT IDENTIFIER
- SQUENTIAL NUMBER

SHORT DESC.
(TWO LINES)
AAA-b

DATA DEVICE LEGEND

	IT
	OT
	ACCESS CONTROL
	CAMERA
	WIRELESS ACCESS POINT

DEVICE AND JACK IDENTIFIER

AAA-bbBB
- DEVICE DESIGNATOR
- PROCESS FUNCTIONAL AREA NUMBER
- 2-DIGIT SEQUENTIAL DEVICE NUMBER

DEVICE DESIGNATOR

CAM	SECURITY CAMERA
CPU	COMPUTER
CR	CARD READER
DT	PROCESS GENERAL DATA DROP
TV	TV / DISPLAY
WAP	WIRELESS ACCESS POINT

LEGEND

	POWER POLE BY OTHERS
S	SINGLE POLE SINGLE THROW SWITCH (SPST)
	VOICE/DATA OUTLET, BACK BOX AND CONDUIT STUBBED
	DATA OUTLET, PROVIDE (1) CABLE UNLESS NOTED OTHERWISE. # NEXT TO DEVICE INDICATES JACK IDENTIFICATION.
FP	WALL MOUNTED FURNITURE FEED, BACK BOX AND CONDUIT STUBBED ABOVE CEILING OR TO BAR JOISTS BY ELECTRICAL CONTRACTOR. PROVIDE CAT 6A CABLES AS NOTED. # NEXT TO DEVICE INDICATES JACK IDENTIFICATION.
	FLOOR OUTLET, FLOOR BOX AND CONDUIT STUBBED ABOVE CEILING OR TO BAR JOISTS BY ELECTRICAL CONTRACTOR. PROVIDE CAT 6A CABLES AS NOTED. # NEXT TO DEVICE INDICATES JACK IDENTIFICATION.
CR	ELECTRONIC CARD READER
DC	DOOR CONTACT
DDC	DOUBLE DOOR CONTACT
EL	ELECTRIC DOOR LOCK (PROVIDED BY DOOR SUPPLIER)
OH	OVERHEAD DOOR CONTACT
IC	INTERCOM AND CAMERA STATION
EM	REMOTE DOOR RELEASE
PTH	POWER TRANSFER HINGE (PROVIDE BY DOOR SUPPLIER)
C	CAMERA
J	JUNCTION BOX (SIZE PER N.E.C.)

ABBREVIATIONS

AC	ABOVE COUNTER TOP, SEE ARCH ELEVATIONS
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AL	ALUMINUM
ATS	AUTOMATIC TRANSFER SWITH
BATT	BATTERY
BC	BELOW COUNTER
BFF	BELOW FINISHED FLOOR
BFG	BELOW FINISHED GRADE
BOCT	BOTTOM OF CABLE TRAY, MEASUERD FROM FIRST FLOOR SLAB
CMU	CONCRETE MASONRY UNIT
CONC	CONCRETE
CONTR	CONTRACTOR
CPT	CONTROL POWER TRANSFORMER
CT	CURRENT TRANSFORMER
CU	COPPER
DISC	DISCONNECT
DN	DOWN
EF	EXHAUST FAN
EL	ELEVATION
EWC	ELECTRIC WATER COOLER
FVNR	FULL VOLTAGE NON-REVERSING
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
HOA	HAND-OFF-AUTO
IMP	INSULATED METAL PANEL
INST	INSTANTANEOUS
LNS	LINE NETWORK SWITCH
MCC	MOTOR CONTROL CENTER
MDP	MAIN DISTRIBUTION PANEL
MSB	MAIN SWITCHBOARD
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
PNL	PANEL
RCP	REFRIGERATION CONTROL PANEL
RTD	RESISTANCE TEMPERATURE DETECTOR
T/CONC	TOP OF CONCRETE
T/GRATING	TOP OF GRATING
T/M	THERMAL MAGNETIC
TOH	TOP OF HANGER
TYP	TYPICAL
UON	UNLESS NOTED OTHERWISE
V-PH-HZ	VOLTS-PHASE-HERTZ
WP	WEATHERPROOF
XFMR	TRANSFORMER

PROCESS SHEET IDENTIFIER

DX#### ##
- LEVEL 1 DISCIPLINE DESIGNATOR
- LEVEL 2 DISCIPLINE DESIGNATOR
- SHEET TYPE DESIGNATOR
- SHEET SUB-TYPE DESIGNATOR
- 2-DIGIT SEQUENCE DESIGNATOR
- 2-DIGIT SEQUENCE DESIGNATOR
- *SUB-SECTOR DESIGNATOR
- *SECTOR DESIGNATOR
- *AREA DESIGNATOR

*APPLICABLE TO PLANS ONLY

DISCIPLINE DESIGNATOR

DC	PROCESS CONTROLS	DQ	PROCESS EQUIPMENT
DE	PROCESS ELECTRICAL	DT	PROCESS TELECOMMUNICATION
DG	PROCESS GENERAL/OVERALL	DU	PROCESS UTILITIES
DP	PROCESS PIPING	SK	PROCESS SKETCHES

SHEET TYPE DESIGNATOR

0 GENERAL - SYMBOLS, LEGENDS, NOTES, ETC.
1 PLANS
2 ELEVATIONS AND PROFILES
3 SECTIONS
4 LARGE SCALE VIEWS
5 DETAILS
6 SCHEDULES AND DIAGRAMS
7 USER DEFINED
8 USER DEFINED
9 3D REPRESENTATIONS

SHEET SUB-TYPE DESIGNATOR

0 FOUNDATIONS
1 FIRST FLOOR / SLAB
2 ELEVATED FLOOR STRUCTURES AND FRAMING, MEZZANINE
3 INTERSTITIAL SPACE
4 ROOF STRUCTURE / FRAMING
5 ROOF RAISED PLATFORM
6 FIRST FLOOR REFLECTED CEILING
7 ELEVATED FLOOR STRUCTURE AND FRAMING, MEZZANINE REFELCTED CEILING
8 INTERSTITIAL SPACE REFLECTED CEILING (OPTIONAL)

DEMOLITION DRAWINGS

DDX#### ##
- INDICATES DEMOLITION DRAWING

OWNER

EST. 2007 Vital FARMS®

PROJECT INFORMATION

VITAL FARMS
EGG CENTRAL 2
SEYMOUR,IN

stellar
TAKING SOLUTIONS FURTHER

OPERATING AS:
THE STELLAR GROUP
2900 HARTLEY ROAD, JACKSONVILLE, FL 32257 (904) 260-2900
WWW.STELLAR.NET

SEAL

Professional certification. I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed professional architect/engineer under the laws of the state of IN

CONSULTANT

The Stellar Group, Inc.
All rights reserved. No part of this work may be used, reproduced, distributed, displayed, or otherwise communicated in any form or by any means without the prior written consent of The Stellar Group, Inc.

REVISIONS

NO.	DESCRIPTION	DATE
A	DESIGN DEVELOPMENT 2	12/12/2025
B	ISSUED FOR BID	01/16/2026
C	REVISED FOR BID	02/06/2026

DATE ISSUED:	12/12/2025
DESIGNED BY:	KDK
REVIEWED BY:	MAM
A/E/OR:	
PROJECT NUMBER:	07645

SHEET TITLE

PROCESS TELECOMMUNICATION GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS

SHEET ID

DT0001

2/7/2026 12:59:05 AM Autodesk Docs://07645_Vital Farms Egg Central Station 2/07645_VF EGG STA 2_D_R23.rvt