CIRCUIT SCHEDULE - OT

MDF / IDF	SWITCH	PORT	CIRCUIT DESCRIPTION	LENGTH	COMMENTS
202	202OT-SW01	1	PNL20002 - TEMPERING PALLET CONVEYORS PANEL	153'	
202	202OT-SW01	2	PNL20106 - EGG DRYER CONTROL PANEL	51'	
202	202OT-SW01	3	PNL20109 - WALCHEM I-9 CONTROLLER	51'	
202	202OT-SW01	4	PNL20103 - EGG WASHER CONTROL PANEL	64'	
202	202OT-SW01	5	PNL20104 - EGG GRADER CONTROL PANEL	99'	
202	202OT-SW01	6	PNL20105 - CASE PACK TAKEAWAY CONTROL PANEL	177'	
202	202OT-SW01	7	PNL20108 - QC CONVEYOR PANEL	151'	
202	202OT-SW01	8	PNL20110 - EGG WASH DOSING CONTROL BOX	46'	
202	202OT-SW01	9	PNL20112 - CIP DOSING CONTROL BOX	49'	
202	202OT-SW01	10	PNL20113 - PROCESS DATA PANEL	57'	
202	202OT-SW01	11	CER20101 - CASE ERECTOR	142'	
202	202OT-SW01	12	CER20102 - CASE ERECTOR	148'	
202	202OT-SW01	13	CER20103 - CASE ERECTOR	153'	
202	202OT-SW01	14	CER20104 - CASE ERECTOR	159'	
202	202OT-SW01	15	CER20105 - CASE ERECTOR	162'	
202	202OT-SW01	16	CER20106 - CASE ERECTOR	167'	
202	202OT-SW01	17	CER20107 - CASE ERECTOR	173'	
202	202OT-SW01	18	CER20108 - CASE ERECTOR	178'	
202	202OT-SW01	19	MSE20101 - OPERATOR STATION	118'	
202	202OT-SW01	20	MSE20102 - OPERATOR STATION	123'	
202	202OT-SW01	21	MSE20103 - OPERATOR STATION	167'	
202	202OT-SW01	22	MSE20104 - OVOTRACK PC STATION	165'	
202	202OT-SW01	23	MSE20105 - OPERATOR STATION	103'	
202	202OT-SW01	24	MSE20106 - OVOTRACK PC STATION	100'	
202	202OT-SW01	25	QCS20101 - QC ONLINE WORKSTATION	132'	
202	202OT-SW01	26	QCS20102 - QC ONLINE WORKSTATION	137'	
202	202OT-SW01	27	QCL20101 - QC CHECK / LAB	134'	
202	202OT-SW01	28	QCL20102 - QC CHECK / LAB	139'	
202	202OT-SW01	29	SNN20101 - OVOTRACK FIXED CASE SCANNER	169'	
202	202OT-SW01	30	SNN20102 - OVOTRACK FIXED CASE SCANNER	157'	
202	202OT-SW01	31	CIP20101 - EGG GRADER CIP	96'	
202	202OT-SW01	32	WSR20102 - PARTS WASHER	47'	
202	202OT-SW01	33	RTU-2 - ROOF TOP UNIT #2	95'	

202: 33

203	203OT-SW01	1	PNL20203 - EGG WASHER CONTROL PANEL	64'	
203	203OT-SW01	2	PNL20204 - EGG GRADER CONTROL PANEL	95'	
203	203OT-SW01	3	PNL20205 - CASE PACK TAKEAWAY CONTROL PANEL	175'	
203	203OT-SW01	4	PNL20206 - EGG DRYER CONTROL PANEL	50'	
203	203OT-SW01	5	PNL20208 - QC CONVEYOR PANEL	138'	
203	203OT-SW01	6	PNL20209 - WALCHEM I-9 CONTROLLER	50'	
203	203OT-SW01	7	PNL20210 - EGG WASH DOSING CONTROL BOX	45'	
203	203OT-SW01	8	PNL20212 - CIP DOSING CONTROL BOX	48'	
203	203OT-SW01	9	PNL20213 - PROCESS DATA PANEL	56'	
203	203OT-SW01	10	PNL40001 - ACCUMULATION CONVEYOR SYSTEM PANEL PLC	193'	
203	203OT-SW01	11	PNL40001 - ACCUMULATION CONVEYOR SYSTEM PANEL HMI	194'	
203	203OT-SW01	12	CER20201 - CASE ERECTOR	143'	
203	203OT-SW01	13	CER20202 - CASE ERECTOR	149'	
203	203OT-SW01	14	CER20203 - CASE ERECTOR	155'	
203	203OT-SW01	15	CER20204 - CASE ERECTOR	160'	
203	203OT-SW01	16	CER20205 - CASE ERECTOR	159'	
203	203OT-SW01	17	CER20206 - CASE ERECTOR	165'	
203	203OT-SW01	18	CER20207 - CASE ERECTOR	170'	
203	203OT-SW01	19	CER20208 - CASE ERECTOR	176'	
203	203OT-SW01	20	MSE20201 - OPERATOR STATION	116'	
203	203OT-SW01	21	MSE20202 - OPERATOR STATION	121'	
203	203OT-SW01	22	MSE20203 - OPERATOR STATION	165'	
203	203OT-SW01	23	MSE20204 - OVOTRACK PC STATION	163'	
203	203OT-SW01	24	MSE20205 - OPERATOR STATION	95'	
203	203OT-SW01	25	MSE20206 - OVOTRACK PC STATION	98'	
203	203OT-SW01	26	MSE40201 - OVOTRACK PC STATION WITH PRINTER	167'	
203	203OT-SW01	27	QCS20201 - QC ONLINE WORKSTATION	125'	
203	203OT-SW01	28	QCL20201 - QC CHECK / LAB	133'	
203	203OT-SW01	29	QCL20202 - QC CHECK / LAB	127'	
203	203OT-SW01	30	SNN20201 - OVOTRACK FIXED CASE SCANNER	138'	
203	203OT-SW01	31	SNN20202 - OVOTRACK FIXED CASE SCANNER	150'	
203	203OT-SW01	32	CIP20201 - EGG GRADER CIP	94'	
203	203OT-SW01	33	WSR20202 - PARTS WASHER	45'	
203	203OT-SW01	34	SCL20101 - FLOOR SCALE	175'	
203	203OT-SW01	35	PAWI40301 - PALLET WRAPPER	139'	

203	203OT-SW02	1	ACT-1	240'	
203	203OT-SW02	2	FM-C2 - FLOW METER	213'	
203	203OT-SW02	3	FM-C3 - FLOW METER	186'	
203	203OT-SW02	4	FM-W8 - FLOW METER	211'	
203	203OT-SW02	5	FM-W9 - FLOW METER	210'	
203	203OT-SW02	6	FM-W10 - FLOW METER	209'	
203	203OT-SW02	7	FM-W11 - FLOW METER	187'	
203	203OT-SW02	8	FM-W12 - FLOW METER	188'	
203	203OT-SW02	9	FM-W13 - FLOW METER	191'	
203	203OT-SW02	10	RCU-1 - REFRIGERATION CONDENSING UNIT #1 - NEST RUN STORAGE	237'	
203	203OT-SW02	11	RCU-2 - REFRIGERATION CONDENSING UNIT #2 - NEST RUN STORAGE	202'	
203	203OT-SW02	12	RCU-3 - REFRIGERATION CONDENSING UNIT #3 - NEST RUN STORAGE	174'	
203	203OT-SW02	13	RCU-12 - REFRIGERATION CONDENSING UNIT #12 - PALLET STORAGE	159'	
203	203OT-SW02	14	RCU-13 - REFRIGERATION CONDENSING UNIT #13 - PALLET STORAGE	203'	
203	203OT-SW02	15	RTU-3 - ROOF TOP UNIT #3	83'	

203: 50

204	204OT-SW01	1	PNL10001 - VERTICAL CONVEYOR PANEL	231'	
204	204OT-SW01	2	PNL10008 - VERTICAL CONVEYOR PANEL	228'	
204	204OT-SW01	3	MSE10103 - OVOTRACK PC STATION WITH PRINTER	218'	
204	204OT-SW01	4	SCN10001 - OVOTRACK TV	260'	

204: 4

205	205OT-SW01	1	MSE10105 - OVOTRACK PC STATION WITH PRINTER	193'	
205	205OT-SW01	2	MSE40101 - OVOTRACK PC STATION WITH PRINTER	104'	
205	205OT-SW01	3	MSE40301 - OVOTRACK PC STATION WITH PRINTER	330'	
205	205OT-SW01	4	SNN10106 - OVOTRACK PALLET SCAN STATION	193'	
205	205OT-SW01	5	SNN40101 - OVOTRACK FIXED CASE SCANNER	157'	
205	205OT-SW01	6	SNN40102 - OVOTRACK FIXED PALLET SCANNER	155'	
205	205OT-SW01	7	SNN40201 - OVOTRACK FIXED CASE SCANNER	165'	
205	205OT-SW01	8	SNN40202 - OVOTRACK FIXED PALLET SCANNER	114'	
205	205OT-SW01	9	MPC40101 - MECHANICAL PALLETIZER	129'	
205	205OT-SW01	10	MPC40201 - MECHANICAL PALLETIZER	155'	
205	205OT-SW01	11	PAWI40101 - PALLET WRAPPER	90'	
205	205OT-SW01	12	PAWI40201 - PALLET WRAPPER	123'	
205	205OT-SW01	13	PNL10006 - VERTICAL CONVEYOR PANEL	180'	
205	205OT-SW01	14	RCU-8 - REFRIGERATION CONDENSING UNIT #8 - FINISHED GOODS	260'	
205	205OT-SW01	15	RCU-9 - REFRIGERATION CONDENSING UNIT #9 - FINISHED GOODS	244'	
205	205OT-SW01	16	RCU-10 - REFRIGERATION CONDENSING UNIT #10 - FINISHED GOODS	228'	
205	205OT-SW01	17	RCU-11 - REFRIGERATION CONDENSING UNIT #11 - FINISHED GOODS	265'	
205	205OT-SW01	18	P-4 - PUMP #4	228'	

205: 18

206	206OT-SW01	1	MSE10104 - OVOTRACK PC STATION WITH PRINTER	160'	
206	206OT-SW01	2	SNN10104 - OVOTRACK WEIGHSCALE SCAN STATION	182'	
206	206OT-SW01	3	PAWI40401 - PALLET WRAPPER	202'	
206	206OT-SW01	4	PNL10005 - VERTICAL CONVEYOR PANEL	136'	
206	206OT-SW01	5	CP-10001 - DOCK LEVELER CONTROL PANEL - RECEIVING DOCK 1302B	207'	
206	206OT-SW01	6	CP-10002 - DOCK LEVELER CONTROL PANEL - RECEIVING DOCK 1302C	188'	
206	206OT-SW01	7	CP-10003 - DOCK LEVELER CONTROL PANEL - RECEIVING DOCK 1302D	170'	
206	206OT-SW01	8	CP-10004 - DOCK LEVELER CONTROL PANEL - RECEIVING DOCK 1302E	152'	
206	206OT-SW01	9	CP-10005 - DOCK LEVELER CONTROL PANEL - RECEIVING DOCK 1302F	133'	
206	206OT-SW01	10	RTU-1 - ROOF TOP UNIT #1 - TRUCKER AREA	121'	
206	206OT-SW01	11	RCU-5 - REFRIGERATION CONDENSING UNIT #5	72'	
206	206OT-SW01	12	RCU-4 - REFRIGERATION CONDENSING UNIT #4	90'	
206	206OT-SW01	13	RCU-6 - REFRIGERATION CONDENSING UNIT #6 - NEST RUN DOCK	111'	
206	206OT-SW01	14	RCU-7 - REFRIGERATION CONDENSING UNIT #7 - FINISHED GOODS DOCK	249'	
206	206OT-SW01	15	P-3 - PUMP #3	201'	
206	206OT-SW01	16	P-2 - PUMP #2	183'	
206	206OT-SW01	17	P-1 - PUMP #1	107'	

206: 17

CIRCUIT SCHEDULE - OT

MDF / IDF	SWITCH	PORT	CIRCUIT DESCRIPTION	LENGTH	COMMENTS
2M11	2M11OT-SW01	1	ACCU-1 - CRAC CONDENSING UNIT #1	83'	
2M11	2M11OT-SW01	2	AHU-6 - AIR HANDLING UNIT #6 - MAIN OFFICE (WEST)	87'	
2M11	2M11OT-SW01	3	AHU-7 - AIR HANDLING UNIT #7 - MAIN OFFICE (EAST)	107'	
2M11	2M11OT-SW01	4	CRAC-1 - SPLIT SYSTEM AIR HANDLING UNIT - MDF RM	76'	
2M11	2M11OT-SW01	5	ERV-3 - ENERGY RECOVERY UNIT #3	63'	
2M11	2M11OT-SW01	6	FPB-4-1 - AIR TERMINAL UNIT	134'	
2M11	2M11OT-SW01	7	FPB-4-2 - AIR TERMINAL UNIT	116'	
2M11	2M11OT-SW01	8	FPB-4-3 - AIR TERMINAL UNIT	56'	
2M11	2M11OT-SW01	9	FPB-4-4 - AIR TERMINAL UNIT	95'	
2M11	2M11OT-SW01	10	FPB-4-5 - AIR TERMINAL UNIT	116'	
2M11	2M11OT-SW01	11	FPB-4-6 - AIR TERMINAL UNIT	140'	
2M11	2M11OT-SW01	12	FPB-4-7 - AIR TERMINAL UNIT	97'	
2M11	2M11OT-SW01	13	FPB-4-8 - AIR TERMINAL UNIT	103'	
2M11	2M11OT-SW01	14	FPB-4-9 - AIR TERMINAL UNIT	85'	
2M11	2M11OT-SW01	15	FPB-5-1 - AIR TERMINAL UNIT	148'	
2M11	2M11OT-SW01	16	FPB-5-2 - AIR TERMINAL UNIT	182'	
2M11	2M11OT-SW01	17	FPB-5-3 - AIR TERMINAL UNIT	197'	

2M11: 17

2M21	2M21OT-SW01	1	AC-1 - UTILITY AIR COMPRESSOR 1	188'	
2M21	2M21OT-SW01	2	AC-2 - UTILITY AIR COMPRESSOR 2	180'	
2M21	2M21OT-SW01	3	AC-3 - UTILITY AIR COMPRESSOR 3	171'	
2M21	2M21OT-SW01	4	ACCU-2 - CRAC CONDENSING UNIT #2	108'	
2M21	2M21OT-SW01	5	AD-1 - REFRIGERATED AIR DRYER #1	155'	
2M21	2M21OT-SW01	6	AD-2 - REFRIGERATED AIR DRYER #2	149'	
2M21	2M21OT-SW01	7	AD-3 - REFRIGERATED AIR DRYER #3	143'	
2M21	2M21OT-SW01	8	B-1 - CLOSED LOOP HOT WATER BOILER #1	163'	
2M21	2M21OT-SW01	9	B-2 - CLOSED LOOP HOT WATER BOILER #2	155'	
2M21	2M21OT-SW01	10	B-3 - CLOSED LOOP HOT WATER BOILER #3	148'	
2M21	2M21OT-SW01	11	CH-1 - CHILLER #1	114'	
2M21	2M21OT-SW01	12	FM-C1 - FLOW METER	138'	
2M21	2M21OT-SW01	13	FM-W1 - FLOW METER	195'	
2M21	2M21OT-SW01	14	FM-W2 - FLOW METER	176'	
2M21	2M21OT-SW01	15	FM-W3 - FLOW METER	168'	
2M21	2M21OT-SW01	16	FM-W6 - FLOW METER	160'	
2M21	2M21OT-SW01	17	FM-W7 - FLOW METER	105'	
2M21	2M21OT-SW01	18	FPB-2-2 - AIR TERMINAL UNIT	65'	
2M21	2M21OT-SW01	19	GWH-1 - PROCESS GAS WATER HEATER #1	144'	
2M21	2M21OT-SW01	20	GWH-2 - PROCESS GAS WATER HEATER #2	133'	
2M21	2M21OT-SW01	21	GWH-3 - PROCESS GAS WATER HEATER #3	125'	
2M21	2M21OT-SW01	22	GWH-4 - PROCESS GAS WATER HEATER #4	122'	
2M21	2M21OT-SW01	23	GWH-5 - PROCESS GAS WATER HEATER #5	116'	
2M21	2M21OT-SW01	24	GWH-6 - PROCESS GAS WATER HEATER #6	111'	
2M21	2M21OT-SW01	25	P-C1 - CHILLED WATER RETURN PUMP	133'	
2M21	2M21OT-SW01	26	P-C2 - CHILLED WATER RETURN PUMP	128'	
2M21	2M21OT-SW01	27	P-D1 - DOMESTIC HOT WATER PUMP #1	131'	
2M21	2M21OT-SW01	28	P-D2 - DOMESTIC HOT WATER PUMP #2	126'	
2M21	2M21OT-SW01	29	P-H1 - HOT WATER CIRCULATION PUMP #1	154'	
2M21	2M21OT-SW01	30	P-H2 - HOT WATER CIRCULATION PUMP #2	144'	
2M21	2M21OT-SW01	31	P-P1 - PROCESS HOT WATER PUMP #1	119'	
2M21	2M21OT-SW01	32	P-P2 - PROCESS HOT WATER PUMP #2	115'	
2M21	2M21OT-SW01	33	P-W4 - PUMP	128'	
2M21	2M21OT-SW01	34	P-W5 - PUMP	116'	
2M21	2M21OT-SW01	35	SF-1	120'	
2M21	2M21OT-SW01	36	SF-2	119'	
2M21	2M21OT-SW01	37	SF-3	164'	
2M21	2M21OT-SW01	38	WPB-1 - DOMESTING WATER SUPPLY BOOSTER PUMP SKID	177'	
2M21	2M21OT-SW01	39	WS-1 - WATER SOFTENER CONTROL PANEL	166'	

2M21	2M21OT-SW02	1	AHU-1 - AIR HANDLING UNIT #1	101'	
2M21	2M21OT-SW02	2	AHU-2 - AIR HANDLING UNIT #2	69'	
2M21	2M21OT-SW02	3	AHU-3 - AIR HANDLING UNIT #3	131'	
2M21	2M21OT-SW02	4	AHU-4 - AIR HANDLING UNIT #4	172'	
2M21	2M21OT-SW02	5	AHU-5 - AIR HANDLING UNIT #5	224'	
2M21	2M21OT-SW02	6	CRAC-2 - SPLIT SYSTEM AIR HANDLING UNIT - MDF RM	81'	
2M21	2M21OT-SW02	7	ERV-1 - ENERGY RECOVERY UNIT #1	119'	
2M21	2M21OT-SW02	8	ERV-2 - ENERGY RECOVERY UNIT #2	182'	
2M21	2M21OT-SW02	9	FPB-2-1 - AIR TERMINAL UNIT	66'	
2M21	2M21OT-SW02	10	FPB-2-3 - AIR TERMINAL UNIT	78'	
2M21	2M21OT-SW02	11	FPB-2-4 - AIR TERMINAL UNIT	124'	
2M21	2M21OT-SW02	12	FPB-2-5 - AIR TERMINAL UNIT	146'	
2M21	2M21OT-SW02	13	FPB-2-6 - AIR TERMINAL UNIT	143'	
2M21	2M21OT-SW02	14	UCP-1 - UTILITIES CONTROL PANEL	111'	

2M21	2M21OT-SW03	1	PNL20107 - OVERHEAD CASE CONVEYORS PANEL	201'	
2M21	2M21OT-SW03	2	PNL20207 - OVERHEAD CASE CONVEYORS PANEL	204'	
2M21	2M21OT-SW03	3	PNL30001 - CHEMICAL SKID CONTROL PANEL	164'	
2M21	2M21OT-SW03	4	PNL30002 - WALCHEM I-9 CONTROLLER	167'	
2M21	2M21OT-SW03	5	PNL50004 - TRAY WASHER CONTROL PANEL	130'	
2M21	2M21OT-SW03	6	PNL50006 - TRAY WASHER CONTROL PANEL	143'	
2M21	2M21OT-SW03	7	PNL50008 - TRAY WASHER CONTROL PANEL	157'	
2M21	2M21OT-SW03	8	PNL50010 - WASHER DOSING CONTROL BOX	98'	
2M21	2M21OT-SW03	9	PNL50011 - WALCHEM I-9 CONTROLLER	102'	
2M21	2M21OT-SW03	10	PNL50000 - PROCESS DATA PANEL	118'	
2M21	2M21OT-SW03	11	COP30001 - COP TANK	177'	
2M21	2M21OT-SW03	12	COP30002 - COP TANK	167'	
2M21	2M21OT-SW03	13	CSR40101 - CASE SEALER	201'	
2M21	2M21OT-SW03	14	CSR40102 - CASE SEALER	217'	
2M21	2M21OT-SW03	15	CSR40201 - CASE SEALER	220'	
2M21	2M21OT-SW03	16	CSR40202 - CASE SEALER	238'	
2M21	2M21OT-SW03	17	WSR50201 - PALLET & DIVIDER WASHER	148'	
2M21	2M21OT-SW03	18	TD-3006 - RJ45 DATA JACK	137'	
2M21	2M21OT-SW03	19	TD-3009 - RJ45 DATA JACK	167'	

2M21: 72

Grand total: 211

OWNER

EST. 2007 Vital FARMS®

PROJECT INFORMATION

VITAL FARMS
EGG CENTRAL 2
SEYMOUR,IN

stellar
TAKING SOLUTIONS FURTHER

OPERATING AS:
THE STELLAR GROUP
2900 HARTLEY ROAD, JACKSONVILLE, FL, 32257 (904) 260-2900
WWW.STELLAR.NET

SEAL

Professional certification. I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed professional architect/engineer under the laws of the state of IN.

CONSULTANT

The Stellar Group, Inc.
All rights reserved. No part of this work may be used, reproduced, distributed, displayed, or otherwise communicated in any form or by any means without the prior written consent of The Stellar Group, Inc.

REVISIONS

NO.	DESCRIPTION	DATE
A	ISSUED FOR BID	01/16/2026
B	REVISED FOR BID	02/06/2026

DATE ISSUED:	12/12/2025
DESIGNED BY:	CDS
REVIEWED BY:	MAM
A/EOR:	
PROJECT NUMBER:	07645

SHEET TITLE

PROCESS TELECOM
CIRCUIT SCHEDULE - OT

SHEET ID

DT6002

2/7/2026 1:00:38 AM Autodesk Docs://07645_Vital Farms Egg Central Station 2/07645_VF EGG STA 2_D_R23.rvt